BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2020-21 Dated: 29-01-2021

APPROVED TENDER SCHEDULE –'B'

Item 05

Name of Work :-Improvements to Roads and Drains at Ambabhavani Layout (Part-1) in Ward No 03

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri Umesh N	
				Rate	Rate in Words
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. As Per the Direction of Engineer In charge of the work.	Cum	986.40	207.60	Two Hundred Seven Paise Sixty Only
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. As Per the Direction of Engineer In charge of the work.	Cum	63.36	5509.33	Five Thousand Five Hundred Nine Paise ThirtyThree Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm.As Per the Direction of Engineer In charge of the work.	Cum	138.24	7189.42	Seven Thousand One Hundred EightyNine Paise FourtyTwo Only

	Providing T.M.T steel reinforcement for R.C.C orkincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.Specification No. KBS 4.6.3.As Per the Direction of Engineer In charge of the work.	Tonne	9.05	65046.90	SixtyFive Thousand FourtySix Paise Ninety Only
5	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortor including form work, lift charges,curing and concrtee finished surface on both sides etc,and complete as per the directions of Enginner in charges.(Data Rate).As Per the Direction of Engineer In charge of the work.	Sqm	345.60	2337.00	Two Thousand Three Hundred ThirtySeven Only
6	Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter 3. As Per the Direction of Engineer In charge of the work.	Sqm	2256.00	6.36	Six Paise ThirtySix Only
7	Providing, laying, spreading and compacting cushed stone aggregates of granite / trap I basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve thedesired density complete as per specifications. MORTH Specification No. 406.As Per the Direction of Engineer In charge of the work.	Cum	451.20	2001.28	Two Thousand One Paise TwentyEight Only
8	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg I sqm using mechanical means complete as per specifications.MORTH Specification No. 502.As Per the Direction of Engineer In charge of the work.	Sqm	2256.00	29.68	TwentyNine Paise SixtyEight Only

Ubsh.N

	providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications.. MORTH Specification No. 507 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen. As Per the Direction of Engineer In charge of the work.	Cum	112.80	6407.70	Six Thousand Four Hundred Seven Paise Seventy Only
10	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH specification clause 501.As Per the Direction of Engineer In charge of the work.	Sqm	2256.00	5.30	Five Paise Thirty Only
11	Providing and applying tack coat using 80/100 grade bitumen(VGIO) on the prepared black topped surfaces at 2.5 kg per 10sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per spcifications.MORTH.As Per the Direction of Engineer In charge of the work.	Sqm	2256.00	12.72	Twelve Paise SeventyTwo Only
12	Providing and laying bituminous concrete 40 mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. MORTH Specification No. 509 - using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 40 mm) with 5.4 % VG-30 Bitumen.As Per the Direction of Engineer In charge of the work.	Cum	90.24	7355.34	Seven Thousand Three Hundred FiftyFive Paise ThirtyFour Only

Ushas.N
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.